

## Conventional Woven Wire Fence

ITEM	UNIT	PRICE	CONV. WOVEN WIRE FARM CUT POSTS 1047-6-11 + 1 TOP BARBED WIRE		CONV. WOVEN WIRE TREATED POSTS 1047-6-11 + 1 TOP BARBED WIRE		H. T. WOVEN WIRE TREATED POSTS 1047-6-12 1/2 + 1 TOP BARBED WIRE	
			QUANTITY	TOTAL	QUANTITY	TOTAL	QUANTITY	TOTAL
8 FT BRACE POSTS 6"-7"	EACH	\$13.03	0.00	\$0.00	16.00	\$208.45	16.00	\$208.45
7 FT LINE POSTS 4"-5"	EACH	\$7.27	0.00	\$0.00	72.00	\$523.17	72.00	\$523.17
8 FT BRACES 4"-5"	EACH	\$7.76	0.00	\$0.00	12.00	\$93.08	12.00	\$93.08
8 FT FARM CUT LOCUST POSTS	EACH	\$6.51	100.00	\$651.41	0.00	\$0.00	0.00	\$0.00
WIRE CONV. 1047-6-11 20 ROD	ROLL	\$264.35	3.03	\$801.06	3.03	\$801.06	0.00	\$0.00
WIRE HT 1047-6-12.5 20 ROD	ROLL	\$182.48	0.00	\$0.00	0.00	\$0.00	3.03	\$552.96
BARBED WIRE - CONV. 12.5	ROLL	\$82.77	0.80	\$66.21	0.80	\$66.21	0.00	\$0.00
BARBED WIRE - H. T. 15.5	ROLL	\$43.19	0.00	\$0.00	0.00	\$0.00	0.80	\$34.55
FARM GATE - 14 Ft	EACH	\$115.86	1.00	\$115.86	1.00	\$115.86	1.00	\$115.86
GATE HANGING BOLTS	EACH	\$10.29	2.00	\$20.58	2.00	\$20.58	2.00	\$20.58
BRACE PINS - 10"	EACH	\$0.77	8.00	\$6.12	8.00	\$6.12	8.00	\$6.12
BRACE PINS - 5"	EACH	\$0.55	6.00	\$3.29	6.00	\$3.29	6.00	\$3.29
BRACE WIRE - H. TENSILE	FOOT	\$0.039	480.00	\$18.68	480.00	\$18.68	480.00	\$18.68
TWIST STICKS 2 FT	EACH	\$4.81	12.00	\$57.73	12.00	\$57.73	12.00	\$57.73
STAPLES - BARBED FOR HT	LBS.	\$1.91	0.00	\$0.00	0.00	\$0.00	15.25	\$29.17
STAPLES - STANDARD	LBS.	\$1.58	12.22	\$19.32	10.75	\$17.00	0.00	\$0.00
POST DRIVING (MACH & LABOR)	HOURS	\$55.83	11.67	\$651.35	9.33	\$521.08	9.33	\$521.08
LABOR	HOURS	\$18.03	29.93	\$539.70	29.93	\$539.70	29.93	\$539.70
OTHER		\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
<b>TOTALS</b>				\$1,760.27		\$1,931.25		\$1,663.64
	<b>MATERIAL COST PER 1000 FEET</b>			<b>\$1.76</b>		<b>\$1.93</b>		<b>\$1.66</b>
	<b>LABOR COSTS PER 1000 FEET</b>			\$1,191.05		\$1,060.78		\$1,060.78
	<b>LABOR COSTS PER FOOT</b>			<b>\$1.19</b>		<b>\$1.06</b>		<b>\$1.06</b>
	<b>TOTAL COST PER 1000 FEET</b>			\$2,951.32		\$2,992.02		\$2,724.42
	<b>TOTAL COST PER FOOT</b>			<b>\$2.95</b>		<b>\$2.99</b>		<b>\$2.72</b>

### Assumptions

1000 Feet of Fence  
 Double Brace Assembly on each end  
 Equivalent of 2 corners or 4 dips/rises  
 8 Ft between brace posts  
 12 Ft between line posts  
 All brace posts driven 48" in ground

### Labor Requirements

Building Brace Assemblies - Double Span = 1.25 Hours  
 Driving Line Posts = 6 minutes per post  
 Driving Brace Posts = 8 minutes per post  
 Driving Farm Cut Posts = 7 minutes per post  
 Stapling Fence and Barbed Wire = 7 (6+1) minutes per post  
 Unroll and Stretch Fence and Barbed Wire = 0.7 minutes per foot