

**BARBED WIRE**

ITEM	UNIT	PRICE	BARBED HIGH TENSILE 3 STRAND		BARBED HIGH TENSILE 4 STRAND		BARBED HIGH TENSILE 5 STRAND		CONV. BARBED FARM CUT POSTS 4 STRAND		CONV. BARBED FARM CUT POSTS 5 STRAND	
			QUANTITY	TOTAL	QUANTITY	TOTAL	QUANTITY	TOTAL	QUANTITY	TOTAL	QUANTITY	TOTAL
8 FT BRACE POSTS 6"-7"	EACH	\$13.03	10.00	\$130.28	10.00	\$130.28	10.00	\$130.28	0.00	\$0.00	0.00	\$0.00
7 FT LINE POSTS 4"-5"	EACH	\$7.27	35.00	\$254.32	35.00	\$254.32	35.00	\$254.32	0.00	\$0.00	0.00	\$0.00
8 FT BRACES 4"-5"	EACH	\$7.76	6.00	\$46.54	6.00	\$46.54	6.00	\$46.54	0.00	\$0.00	0.00	\$0.00
8 FT FARM CUT LOCUST POSTS	EACH	\$6.51	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	100.00	\$651.41	100.00	\$651.41
BRACE PINS - 10"	EACH	\$0.77	6.00	\$4.59	6.00	\$4.59	6.00	\$4.59	6.00	\$4.59	0.00	\$0.00
BRACE PINS - 5"	EACH	\$0.55	6.00	\$3.29	6.00	\$3.29	6.00	\$3.29	6.00	\$0.00	0.00	\$0.00
BRACE WIRE - H. TENSILE	FOOT	\$0.039	240.00	\$9.34	240.00	\$9.34	240.00	\$9.34	240.00	\$9.34	240.00	\$9.34
HIGH TENSILE BARBED WIRE	ROLL	\$43.19	2.27	\$98.15	3.03	\$130.86	3.79	\$163.58	0.00	\$0.00	0.00	\$0.00
CONVENTIONAL BARBED WIRE	ROLL	\$82.77	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	3.03	\$250.81	3.79	\$313.51
FARM GATE - 14 Ft	EACH	\$115.86	1.00	\$115.86	1.00	\$115.86	1.00	\$115.86	1.00	\$115.86	1.00	\$115.86
GATE HANGING BOLTS	EACH	\$10.29	2.00	\$20.58	2.00	\$20.58	2.00	\$20.58	2.00	\$20.58	2.00	\$20.58
TWIST STICKS 2 FT (PTP)	EACH	\$4.81	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	6.00	\$28.86	6.00	\$28.86
BATTENS 40"	EACH	\$3.24	38.00	\$123.21	38.00	\$123.21	38.00	\$123.21	0.00	\$0.00	0.00	\$0.00
BATTEN CLIPS	EACH	\$0.08	114.00	\$8.90	152.00	\$11.86	190.00	\$14.83	0.00	\$0.00	0.00	\$0.00
STAPLES - BARBED FOR HT	LBS	\$1.91	2.13	\$4.07	2.84	\$5.42	3.55	\$6.78	0.00	\$0.00	0.00	\$0.00
STAPLES - STANDARD	LBS	\$1.58	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00	4.18	\$6.60	5.22	\$8.26
POST DRIVING (MACH & LABOR)	HOURS	\$55.83	4.83	\$269.85	4.83	\$269.85	4.83	\$269.85	10.97	\$612.27	10.97	\$612.27
LABOR	HOURS	\$18.03	10.72	\$193.33	12.22	\$220.37	13.72	\$247.42	13.73	\$247.54	15.96	\$287.79
<b>TOTALS</b>				<b>MATERIAL COST PER 1000 FEET</b>	\$819.13		\$856.17	\$893.20		\$1,088.06		\$1,147.82
				<b>MATERIAL COST PER FOOT</b>	<b>\$0.82</b>		<b>\$0.86</b>	<b>\$0.89</b>		<b>\$1.09</b>		<b>\$1.15</b>
				<b>LABOR COSTS PER 1000 FEET</b>	\$463.17		\$490.22	\$517.26		\$859.81		\$900.06
				<b>LABOR COSTS PER FOOT</b>	<b>\$0.46</b>		<b>\$0.49</b>	<b>\$0.52</b>		<b>\$0.86</b>		<b>\$0.90</b>
				<b>TOTAL COST PER 1000 FEET</b>	\$1,282.30		\$1,346.39	\$1,410.47		\$1,947.87		\$2,047.87
				<b>TOTAL COST PER FOOT</b>	<b>\$1.28</b>		<b>\$1.35</b>	<b>\$1.41</b>		<b>\$1.95</b>		<b>\$2.05</b>

**Assumptions**

1000 Feet of Fence  
 Single Brace Assembly on each end  
 Equivalent of 2 corners or 4 dips/rises  
 8 Ft between brace posts  
 25 Ft between line posts - HT  
 1 batton between line posts - HT  
 12 Ft between line posts - non HT  
 All brace posts driven 48" in ground

**Labor Requirements**

Building Brace Assemblies - Single Span = .75 Hours  
 Driving Line Posts = 6 minutes per post  
 Driving Brace Posts = 8 minutes per post  
 Driving Farm Cut Posts = 7 minutes per post  
 Stapling Wire - 1 minute per staple

**Wire Spacing (Inches) - Ground up**

3 Wire - 13-11-12  
 4 Wire - 6-7-10-12  
 5 Wire - 6-7-8-9-10