

## High Tensile Fixed Knot Fence

HT WOVEN WIRE  
FARM CUT POSTS  
949-12-330 + 1  
TOP BARBED WIRE

HT WOVEN WIRE  
TREATED POSTS  
949-12-330 + 1  
TOP BARBED WIRE

HT WOVEN WIRE  
TREATED POSTS  
949-12-330  
FENCE ONLY

ITEM	UNIT	PRICE	QUANTITY	TOTAL	QUANTITY	TOTAL	QUANTITY	TOTAL
8 FT BRACE POSTS 6"-7"	EACH	\$13.03	0.00	\$0.00	16.00	\$208.45	16.00	\$208.45
7 FT LINE POSTS 4"-5"	EACH	\$7.27	0.00	\$0.00	43.00	\$312.45	43.00	\$312.45
12 FT BRACES 4"-5"	EACH	\$15.95	4.00	\$63.78	4.00	\$63.78	4.00	\$63.78
8 FT FARM CUT LOCUST POSTS	EACH	\$6.51	59.00	\$384.33	0.00	\$0.00	0.00	\$0.00
WIRE CONV. 1047-6-11 330 FT	ROLL	\$264.35	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
WIRE HT 1047-6-12.5 330 FT	ROLL	\$182.48	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
WIRE HT 949-12-330 Fixed Knot	ROLL	\$148.51	3.00	\$445.52	3.00	\$445.52	3.00	\$445.52
BARBED WIRE - H. T. 15 1/2	ROLL	\$43.19	0.80	\$34.55	0.80	\$34.55	0.00	\$0.00
FARM GATE - 14 Ft	EACH	\$115.86	1.00	\$115.86	1.00	\$115.86	0.00	\$0.00
GATE HANGING BOLTS	EACH	\$10.29	2.00	\$20.58	2.00	\$20.58	0.00	\$0.00
BRACE PINS - 10"	EACH	\$0.77	8.00	\$6.12	8.00	\$6.12	8.00	\$6.12
BRACE PINS - 5"	EACH	\$0.55	6.00	\$3.29	6.00	\$3.29	6.00	\$3.29
BRACE WIRE - H. TENSILE	FOOT	\$0.039	240.00	\$9.34	240.00	\$9.34	240.00	\$9.34
INLINE STRAINERS	EACH	\$4.81	2.00	\$9.62	2.00	\$9.62	2.00	\$9.62
STAPLES - BARBED FOR HT	LBS.	\$1.91	0.00	\$0.00	9.30	\$17.78	8.37	\$16.00
STAPLES - STANDARD	LBS.	\$1.58	8.52	\$13.47	0.00	\$0.00	0.00	\$0.00
POST DRIVING (MACH & LABOR)	HOURS	\$55.83	6.88	\$384.30	6.43	\$359.17	6.43	\$359.17
LABOR	HOURS	\$18.03	22.05	\$397.56	19.05	\$343.47	14.57	\$262.64
OTHER		\$0.00	0.00	\$0.00	0.00	\$0.00	0.00	\$0.00
<b>TOTALS</b>				\$1,106.47		\$1,247.35		\$1,074.58
		<b>MATERIAL COST PER 1000 FEET</b>						
		<b>MATERIAL COST PER FOOT</b>		<b>\$1.11</b>		<b>\$1.25</b>		<b>\$1.07</b>
		<b>LABOR COSTS PER 1000 FEET</b>		\$781.86		\$702.64		\$621.81
		<b>LABOR COSTS PER FOOT</b>		<b>\$0.78</b>		<b>\$0.70</b>		<b>\$0.62</b>
		<b>TOTAL COST PER 1000 FEET</b>		\$1,888.33		\$1,949.99		\$1,696.39
		<b>TOTAL COST PER FOOT</b>		<b>\$1.89</b>		<b>\$1.95</b>		<b>\$1.70</b>

### Assumptions

1000 Feet of Fence  
Single Brace Assembly on each end and at Fence Splice  
Equivalent of 2 corners using 8 End Posts  
12 FT between brace posts  
20 FT between line posts  
All brace posts driven 48" in ground

### Labor Requirements

Building Brace Assemblies - Single Span = .75 Hours  
Driving Line Posts = 6 minutes per post  
Driving Brace Posts = 8 minutes per post  
Driving Farm Cut Posts = 7 minutes per post  
Stapling Fence and Barbed Wire = 7 (6+1) minutes per post  
Unroll and Stretch Fence and Barbed Wire = 0.7 minutes per foot